


# Phase II Country Club Towers Apartment Complex NW 68th Avenue and 186th Street Miami, Florida



William A. Eager, A.S.L.A. Lic. # LA0001187






PLANT LIST -		PLANT LIS
	Trees:	
cn - 36 -	Cocos nucifera ' Green Malayan'	alp - 21
	4-14' g.w. staggered hts.	
co - 3 -	Chrysophyllum oliviforme (N) - Satin Leaf	chr -101
	1 0' ht. x 5-6' spr. 5' c.t. 2" cal. full head	
II - 9 -	Ligustrum lucidum - Glossy Privet	con - 24
	1l 0' ht. x 5-6' spr. 5' c.t. 2" cal. full head	
rr – 27 –	Roystonia regia	ixo — 19
	1l 4' g.w. matched	
sm - 76 -	Swetenia mahogani (N) - West Indies Mahogany	phi – 40
	110' ht. x 5-6' spr. 5' c.t. 2" cal. full head	
		pod - 3

planting plan


PLANT LIST —	
	Shrubs and Groundcovers
alp - 217 -	Alpinia z.'Variegata' - Variegated Ginger
	3 gal. 16-18" ht. x spr. full 2' o.c.
chr -1015 -	Chrysobalanus ic. 'Red-Tip' (N) - Red Tip Cocoplum
	3 gal. 24" ht. x 14-16"spr. full 2' o.c.
$con\ -\ 240\ -$	Conocarpus er. 'sericeus' (N) - Silver Buttonwood
	3 gal. 24" ht. x 14-16" spr. full 2' o.c.
ixo — 195 —	Ixora c. 'Nora Grant' - Pink Ixora
	3 gal. 16-18" ht. x spr. full 2' o.c.
phi – 409 –	Philodendron selloum - Split Leaf Philodendron
	3 gal. 16-18" ht. x spr. full 2' o.c.
pod - 31 -	Podocarpus macrophyllus - Yew
	3 gal. 16-18" ht. x spr. full 2' o.c.

ptv - 371 -	Pittosporum t. 'Variegata' - Variegated Pittosporum
	3 gal. 16-18" ht. x spr. full 2' o.c.
rap - 172 -	Raphiolepis in. 'Dwarf Pink' - Dwarf Pink India Hawthorne
	3 gal. 16-18" ht. x spr. full 2' o.c.
$sch\ -\ 235\ -$	Schefflera a. 'Variegata' - Dwarf Variegated Schefflera
	3 gal. 16-18" ht. x spr. full 2' o.c.
sea -1000 -	Seasonal Flowers - Same
	6" pots full 12" o.c.
sod	St. Augustine Flor-tam
	solid sod



Job number

### Country Club Towers Apartment Complex NW 68th Avenue and 186th Street Miami, Florida



EGS2corp.
landscape architecture


5996 S.W. 70th Street South Miami Florida 305 • 274 • 2702 William A. Eager, A.S.L.A. Lic. # LA0001187

L3

## Country Club Towers Apartment Complex NW 68th Avenue and 186th Street Miami, Florida

landscape architecture


William A. Eager, A.S.L.A. Lic. # LA0001187




#### plant specifications

- 1. Landscape Contractor shall be familiar w/ all work required by these drawings. This shall include all grading plans and detail sheets indicating depths of all plantings on the pool deck. If these sheets are not included, contact General Contractor.
- 2. All plant material furnished by the Landscape Contractor unless otherwise specified in Grades and Standards for Nursery Plants, second edition: February 1998, by the Florida Department of Agriculture and Consumer Services Division of the Plant Industry, shall be Florida Grade #1 or better.
- 3. All shrubs and groundcovers shall be guaranteed for 1 year from date of final acceptance. All trees and palms shall be guaranteed for 1 year from date of final acceptance. Sod shall be guaranteed for 90 days from final acceptance.
- 4. Planting soil shall be weed free and consist of 60% clean silica sand, 30% everglades muck and 10% C; anadian peat. All plants shall be installed with planting soil as imdicated on details.
- 5. Landscape Contractor shall be responsible for placement of planting soil on raised pool deck. Soil level as indicated on plans and details shall be after settlement.
- 6. Landscape Contractor shall take all steps required to make all planting beds weed and grass free prior to planting.
- 7. Landscape Contractor shall locate and verify all underground utilities prior to digging.
- 8. All trees shall be staked and/or guyed in a good workmanlike manner as per attached details. No nail staking permitted.
- 9. Any wire guys and/or fabric straps shall be flagged w/ flourescent colored tape as shown in details.
- 10. All trees shall be fertilized at installation w/ "Agriform Pills", 21 gram size, w/ a 20-10-5 formulation., (or approved equal) according to manufacturers recommendations.
- 11. All other plants shall be fertilized at installation w/ "Osmacote" time release pellets (or approved equal) according to manufacturers recommendations.
- 12. All trees in sod areas to have a 30" ring covered w/ a 2" layer of shredded mulch. Cover all shrub beds w/ a 2" layer of
- 13. Sod shall be St. Augustine 'Flor-Tam' (unlesss otherwise noted) laid w/ alternating abutting joints. Sod shall be laid to edge of curb or light of way. Sod in all areas not cowered w/ plant material, paving, gravel or mulch. Sod to be laid level and w/ tight joints. Edges to be clean and smoothly cut to follow outline shown. Landscape Contractor responsible for take-off and 100% coverage of areas.
- 14. Where quantities and/or species differ between the planting plans and plant lists, the plans shall take precedence.
- 15. Landscape Contractor is responsible for doing a take-off of the attached plans. Plant list provided is for guidance only. Landscape Contractor, in submitting a proposal based on these plans, is responsible for all materials as noted on plans.
- 16. Discrepancies shall be brought to the attention of the Landscape Architect.
- 17. No changes shall be made without the prior consent of the Landscape Architect.
- 18. All planting beds shall be treated w/ a pre-emergent herbicide as approved by the Landscape Architect.
- 19. Landscape Contractor is responsible for coordinating with the General Contractor or Owner any and all conditions which may affect the scope of work.
- 20. Landscape contractor shall include in bid all materials and labor as required to complete the job as indicasted on the plans and as directed by the General Contractor. Bidd shall include, filter fabric, drainage mat, protection board, mulch, crane and other equip., etc..
- 21. All plant material shall meet or exceed speciffications listed. but not be limited to, plant materials, planting soil and placement,
- 22. All planted beds shall recieve 100% coverage by a fully automatic irrigation system as per plans.
- 23. Landscape Contractor shall be responsible for providing temporary watering provisions until such time as the irrigation
- 24. All areas labelled mulch/gravel to recieve a 2!" layer of material over a weed barrier material.

#### plant details



palm/large tree planting detail



### landscape legend

requiree for Both Parcels

Zoning District RU4 Net Lot Area 6.74	acres	293,764 s	
OPEN SPACE	REQUIRED	PROVIDED	
A. Square Feet of open space required by Chapter 22, as indicated on site plan:  Net Lot Area = 293,764 s.f. x 40 % = 117,506 s.f.	117,506	6 120,910	
B. Square Feet of parking lot open space required by Chapter 18A, as indicated on site plan:	1490	1490	
No. parking spaces 149 x 10 s.f. per parking space = C. Total s.f. of landscaped open space required by Chapter 33: A+B =	118,996	122,400	
LAWN AREA CALCULATION			
A. 118,486 total s.f. of landscaped open space required by chapter 33	118,486	486 122,400	
B. Maximum lawn area (sod) permitted = 30 % x 118,486 s.f. =	35,545	35,545	
A. No. trees required per net lot acre 28  Less existing number of trees meeting minimum requirements  x trees x x Net Lot Acres	541 1882	189	
B. % Palms allowed: No trees provided x 30%	58	0	
C. % Natives Required: No. trees provided x 30%	58	129	
D. Street Trees (maximum average spacing of 25' o.c palms):  linear feet along street / 35	20	29	
E. Street Trees located directly beneath power lines  (maximum average spacing of 25' o.c.): x linear feet along street/25 =	n/a	na/	
SHRUB3S	_		
	5900		
A. No. trees required 189 x 10 + No. of shrubs required	1940	4823	

ZONING HEARINGS SECTION
MIAMI-DADE PLANNING AND ZONING DEPT.
BY\_\_\_\_\_\_\_

general revision 01.06.04 city comments 12.11.03

plant specifications, details and tabular data

Sheet number

12.5.03

11.03.03

8.25.03

5.15.03